

Sr	Particular	Qty		Measurement			Ded:	Content	Unit	Remark	
				L	B	H					
	Materials							638.69	ft³		
	Cement							118.03	Bags		
	Sand							2.94	Suds		
	Gravel							5.88	Suds		
	Fuel							12.77	Gals		
	Labour										
	Mason							12.77	Nos		
	Worker							76.64	Nos		
	Machine driver							3.19	Nos		
4	<u>9" Thk Brick Work with (1:3) Cement Motar</u>								786.13	ft³	
	Retaining Wall	35		9.25	0.75	3.17		768.91	ft ³		
		1		7.25	0.75	3.17		17.22	ft ³		
	Materials							786.13	ft³		
	Brick							10613.00	Nos		
	Cement							55.00	Bags		
	Sand							2.04	Suds		
	Labour										
	Mason							31.00	Nos		
	Worker							47.00	Nos		
5	<u>4 1/2" Thk Brick Work with (1:3) Cement Motar</u>								1,275.70	ft²	
	Retaining Wall	35		9.25		5.46		1,767.68	ft ²		
		1		7.25		5.46		39.59	ft ²		
		35		6.75		2.25	531.56		ft ²		
	Materials							1,275.70	ft²		
	Brick							7016.34	Nos		
	Cement							34.44	Bags		
	Sand							1.28	Suds		

Sr	Particular	Qty		Measurement			Ded:	Content	Unit	Remark
				L	B	H				
	<i>Labour</i>									
	<i>Mason</i>							25.51	Nos	
	<i>Worker</i>							51.03	Nos	
6	<u>3/4" Thk Plastering Work with 1:2 Cement Motar</u>							5,015.60	ft²	
	Column	38	2	7.67		0.75		437.19	ft ²	
		38	2	0.75		0.54		30.88	ft ²	
		38	2	5.46		0.38		155.61	ft ²	
	Wall	35	2	9.25		7.67		4,964.38	ft ²	
		1	2	7.25		7.67		111.17	ft ²	
		35	2	6.75		2.25	1,063.13		ft ²	
		35	1	18.00		0.21		131.25	ft ²	
		35	1	9.25		0.75		242.81	ft ²	
		1	1	7.25		0.75		5.44	ft ²	
	<i>Materials</i>							5,015.60	ft²	
	<i>Cement</i>							103.00	Bags	
	<i>Sand</i>							3.76	Suds	
	<i>Labour</i>									
	<i>Mason</i>							75.23	Nos	
	<i>Worker</i>							150.47	Nos	
7	<u>Rebar Work</u>									
	Footing, 3/8" dia	38	2	3.03				230.38	Rft	
	Column, 1/2" dia	38	4	11.35				1,725.20	Rft	
	Column, Stir: 1/4" dia	38	20	2.50				1,900.00	Rft	
	P.Beam, 3/8" dia	1	3	382.03				1,146.09	Rft	
	P.Beam, Stir: 1/4" dia 7" c/c	614	1	1.02				626.28	Rft	

