



Sr	Particular	Qty		Measurement			Ded:	Content	Unit	Remark
				L	B	H				
<b>4</b>	<b><u>Rebar Work</u></b>									
	Culvert,5/8"dia(Short),6"C/C	1	15	7.89				118.35	Rft	
	Culvert,1/2"dia(Long),6"C/C	1	57	28.71				1,636.47	Rft	
	Ending, 3/8" dia, 1'9" C/C	1	17	3.00				51.00	Rft	
				<b>Rft</b>	<b>Lb/ft</b>	<b>Lb</b>	<b>Ton</b>			
	<i>5/8" dia MS Rod</i>			118.35	1.043	123	0.055			
	<i>1/2" dia MS Rod</i>			1,636.47	0.668	1,093	0.49			
	<i>3/8" dia MS Rod</i>			51.00	0.376	19	0.009			
	<b>Materials</b>							<b>0.58</b>	<b>Tons</b>	
	<i>5/8" dia</i>							<i>0.06</i>	<i>Tons</i>	
	<i>1/2" dia</i>							<i>0.51</i>	<i>Tons</i>	
	<i>3/8" dia</i>							<i>0.01</i>	<i>Tons</i>	
	<i>Binding Wire</i>							<i>3.22</i>	<i>Viss</i>	
	<b>Labour</b>									
	<i>Steel Fixer</i>							<i>11.59</i>	<i>Nos</i>	
	<i>Worker</i>							<i>11.59</i>	<i>Nos</i>	
<b>5</b>	<b><u>Formwork</u></b>							<b>246.24</b>	<b>ft<sup>2</sup></b>	
	Road (8")	4	1	58.2		0.67		155.12	ft <sup>2</sup>	
		4	1	28.2		0.67		75.12	ft <sup>2</sup>	
		2	1	6.083		0.67		8.11	ft <sup>2</sup>	
		2	1	5.917		0.67		7.89	ft <sup>2</sup>	
	<b>Materials</b>							<b>246.24</b>	<b>ft<sup>2</sup></b>	
	<i>Jungle wood</i>							<i>0.37</i>	<i>Tons</i>	
	<i>5-Plywood(8'x4')</i>							<i>4.24</i>	<i>Sheets</i>	
	<i>Nail</i>							<i>2.05</i>	<i>Viss</i>	

Sr	Particular	Qty		Measurement			Ded:	Content	Unit	Remark
				L	B	H				
	<i>Labour</i>									
	<i>Carpenter</i>							14.77	Nos	
	<i>Worker</i>							7.39	Nos	
	<b>Brick Culvert Work</b>									
<b>6</b>	<b>Earthwork Excavation</b>							<b>3,456.00</b>	<b>ft<sup>3</sup></b>	
		1	1	48.00	18	4.00		3,456.00	ft <sup>3</sup>	
	<i>Labour</i>							<b>3,456.00</b>	<b>ft<sup>3</sup></b>	
	<i>Worker</i>							103.68	Nos	
<b>7</b>	<b>1:2:4 RC Work (12" Thk)</b>							<b>864.00</b>	<b>ft<sup>3</sup></b>	
	Footing	1	1	48.00	18.00	1.00		864.00	ft <sup>3</sup>	
	<i>Materials</i>							<b>864.00</b>	<b>ft<sup>3</sup></b>	
	<i>Cement</i>							159.67	Bags	
	<i>Sand</i>							3.97	Suds	
	<i>Gravel</i>							7.95	Suds	
	<i>Fuel</i>							17.28	Gals	
	<i>Labour</i>									
	<i>Mason</i>							17.28	Nos	
	<i>Worker</i>							103.68	Nos	
	<i>Machine driver</i>							4.32	Nos	
<b>8</b>	<b>Brick Work</b>							<b>1,231.33</b>	<b>ft<sup>3</sup></b>	
	Drain Wall	2	1	28.00	1.50	9.75		819.00	ft <sup>3</sup>	
	Wing Wall									
	Under Ground (18" Thk)	2	2	10.00	1.50	3.00		180.00	ft <sup>3</sup>	
	Above Ground(18" Thk)	2	2	6.00	1.50	4.25		153.00	ft <sup>3</sup>	
	(14" Thk)	2	2	4.00	1.17	4.25		79.33	ft <sup>3</sup>	

