



Sr	Particular	Qty		Measurement			Ded:	Content	Unit	Remark
				L	B	H				
	<b>Materials</b>							<b>39.49</b>	ft <sup>3</sup>	
	Brick							533.00	Nos	
	Cement							3.00	Bags	
	Sand							0.10	Suds	
	<b>Labour</b>									
	Mason							2.00	Nos	
	Worker							2.00	Nos	
<b>4</b>	<b><u>3/4" Thk Plastering with 1:2 Cement Motar</u></b>							<b>1,101.06</b>	ft <sup>2</sup>	
	Column	2	4	7.21		13.50		778.46	ft <sup>2</sup>	
	Ceiling	2	1	31.22		1.50		93.66	ft <sup>2</sup>	
	RC Wall	2	1	44.86				89.72	ft <sup>2</sup>	
	RC Wall	1	1	31.22		0.75		23.42	ft <sup>2</sup>	
	Brick Wall	2	2	9.81		1.50		58.86	ft <sup>2</sup>	
		2	1	11.61		2.00		46.44	ft <sup>2</sup>	
	Side Wall	2	1	1.50		3.50		10.50	ft <sup>2</sup>	
	<b>Materials</b>							<b>1,101.06</b>	ft <sup>2</sup>	
	Cement							23	Bags	
	Sand							0.83	Suds	
	<b>Labour</b>									
	Mason							16.52	Nos	
	Worker							33.03	Nos	
<b>5</b>	<b><u>Rebar Work</u></b>									
	Footing, 1/2" dia	2	14	10.21				285.83	Rft	
	Footing, 1/2" dia	2	14	7.21				201.83	Rft	
	Column, 5/8" dia	2	12	25.06				601.32	Rft	



Sr	Particular	Qty	Measurement			Ded:	Content	Unit	Remark
			L	B	H				
							2	TimeUse	
	<b>Materials</b>						498.88	ft <sup>2</sup>	
	Jungle wood						0.75	Tons	
	5-Plywood(8'x4')						8.58	Sheets	
	Nail						4.16	Viss	
	<b>Labour</b>								
	Carpenter						29.93	Nos	
	Worker						14.97	Nos	
7	<b>Column Head Plastering with 1:2 Cement Motar. (Only Plaster)</b>								
	Col: (24" x 24"), (4 face)	2	15.50						
	RC Wall (9"), (2 face)	1	31.00						
	<b>Labour, Cost</b>		LS				585,000.00		
8	<b>Steel Sliding Door Work</b>						283.50	ft <sup>2</sup>	
		1	28.00		9.00		252.00	ft <sup>2</sup>	
		1	3.50		9.00		31.50	ft <sup>2</sup>	
	<b>Steel Sliding Door Work</b>								
	<b>Material + Labour, Cost</b>		1 Item						
9	<b>Myanmar Moulding Plastering Work. (Only Myanmarmyu)</b>								
	<b>Labour, Cost</b>		1 Item				2,500,000.00		
10	<b>Painting Work. (Emulsion Paint)</b>						1,101.06	ft <sup>2</sup>	
	From Item No (4)						1,101.06	ft <sup>2</sup>	
	<b>Materials</b>						1,101.06	ft <sup>2</sup>	
	Emulsion Paint						11.01	Gals	
	Putty						3.85	Gas	
	2" Brush						2.75	Nos	
	<b>Labour</b>								
	Worker						0.55	Nos	
	Painter						5.51	Nos	